

BILL OF QUANTITIES

Name of Work: Overhauling of 7.5MVA, 33/11KV Power Transformer at 33KV sub-station in IITG Campus						
NIT No: IITG/IPM/NIT/FY21-22/42, Dt-25/02/2022						
SL NO	Description of Items	Unit	Qty	Rate in Figure	Rate in Word	Amount
1.0	Supply, Fitting and Fixing of new 11KV cable Box	Job	1			
2.0	Supply, Fitting and Fixing of LT Bus Bar Connector (Copper)	Set	1			
3.0	Supply, Fitting and Fixing of Silica Jel Breather.	No	1			
4.0	Supply, Fitting and Fixing of 11KV Busbar Insulator.	No	3			
5.0	Filtration & Dehydration of Transformer Oil					
	a). Main Tank	Ltr	6518			
	b). OLTC	Ltr	375			
6.0	Cleaning/de-rusting of Transformer Body, radiator bank, Explosion vent pipe, conservator tank, Marshelling Box etc. then painting with double coat of special Eddy Grey Paints (Including supply of Paints)	No	1			
7.0	Transportation charge of oil filter machine.	LS	1			
Grand Total Amount						
<i>(Rupees Only)</i>						

NOTE: Rates shall be inclusive of all taxes.

Date:

Seal & Signature of bidder