

BOQ
for

Name of Work: Rectification of power failure in AC Panel at New Guest House in IITG Campus.						
NIT NO: IITG/IPM/NIT/R/2024-25/18, Dated: 02.07.2024						
Sl. No.	Description of Item	Unit	Qty.	Rate in Figure (in Rs.)	Rate in Words	Amount (Rs.)
1.0	Supply of 3.5C, 240Sq.mm, 11KV Heavy Duty Armoured XLPE power cable. (Make-KEI/Polycab/Havells/Finolex/RR Kabel)	Mtr	80			
2.0	Supply of 4P, 400Amp 50KA MCCB. (Make-Legrand or equivalent)	No	1			
3.0	Dismantalling of faulty MCCB and installation of new MCCB.	No	1			
3.0	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.					
	a). Above 185 sq. mm and upto 400 sq. mm (clamped with 40x3mm MS flat clamp)	Mtr.	100			
4.0	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.					
	a). 3½ X 300 sq. mm	set	2			
TOTAL AMOUNT						
Discount@.....%, if any						
GRAND TOTAL AMOUNT						

(Rupees.....)

N.B: Quoted rate should be inclusive of all Taxes.

Date:

Place:

Seal & Signature of Bidder