

BILL OF QUANTITY

Name of work: Repainting of few rooms at ground floor of Umium, Barak and Kameng hostel in IITG Campus.

Item No.	Description of item	Unit	Qty	Rate (₹)	Rate (in words)	Amount (₹)
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	Sqm	1946.00			
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	327.32			
3	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :	Sqm	1946.00			
4	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two or more coats	Sqm	1946.00			
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	Sqm	808.38			
	Total Amount ₹ =					-
	Rebate if Any =					-
	Total Amount after rebate ₹ =					-
	Add new GST @ 18.00% =					-
	Total Amount ₹ =					-
	Rounded off =					-

(Rupees Only)