

**Bill of Quantity**  
for

**Provision of Electrification work for campus Wifi Access point in the various location of Academic Complex and Administrative Area.**

Sl. No.	Description of Item	Unit	Qty.	Rate in Figure (in Rs.)	Rate in Word	Amount (Rs.)
1	Wiring of submain wiring with the following size of PVC insulated copper conductor, single core cable in existing PVC casing capping					
	i) 3x1.5 sqmm wire (for light point))	Mtr	50.00			
2	Supply of following types and sizes of 1.1KV grade PVC insulated aluminium conductor armored underground cable make havells/RR Kabel/KEI/Finolex					
	i) 4x6 sqmm	mtr	713.00			
3	Supply and installation of SMC junction box of sizes 295mmx195mmx100mm ( Make Sintex/Hansel	nos.	11.00			
4	Laying one 1100V power cables of following sizes direct in ground including excavation, sand cushioning, protective brick covering and refilling etc. as required					
	i) Up to 35 sqmm	mtr	713.00			

5	Supply and fixing 5amp to 32amps rating,240/415 volt,'C' curve minature breaker suitable for inductive load of following poles in the existing MCB DB complete with connection,testing andcommission etc as required make havells/legrand /schnider					
	a) Single pole (0-32 A SP MCB)	nos.	11.00			
6	Supplying and fixing following modular type switch/socket on the existing swith box/cover including connection etc.as required make legrand or equivalent					
	a) 5 amps switch	pcs	22.00			
	b) 5 amps socket	pcs	22.00			
<b>TOTAL AMOUNT</b>						
Discount @ .....%, if any						
<b>GRAND TOTAL</b>						

Seal  
Date :

Signature of the Tenderer